



## OPEN ACCESS

EDITED BY  
Brian P. Hedlund,  
University of Nevada,  
Las Vegas,  
United States

REVIEWED BY  
Daniel Colman,  
Montana State University,  
United States  
Melody Lindsay,  
Bigelow Laboratory for Ocean Sciences,  
United States

\*CORRESPONDENCE  
Mihaela Glamoclija  
✉ m.glamoclija@rutgers.edu  
Ifeoma R. Ugwuanyi  
✉ ifeoma.ugwuanyi@rutgers.edu

SPECIALTY SECTION  
This article was submitted to  
Extreme Microbiology,  
a section of the journal  
Frontiers in Microbiology

RECEIVED 10 October 2022  
ACCEPTED 06 January 2023  
PUBLISHED 01 February 2023

CITATION  
Ugwuanyi IR, Fogel ML, Bowden R, Steele A,  
De Natale G, Troise C, Somma R, Piochi M,  
Mormone A and Glamoclija M (2023)  
Comparative metagenomics at Solfatara and  
Pisciarelli hydrothermal systems in Italy reveal  
that ecological differences across substrates  
are not ubiquitous.  
*Front. Microbiol.* 14:1066406.  
doi: 10.3389/fmicb.2023.1066406

COPYRIGHT  
© 2023 Ugwuanyi, Fogel, Bowden, Steele,  
De Natale, Troise, Somma, Piochi, Mormone  
and Glamoclija. This is an open-access article  
distributed under the terms of the [Creative Commons Attribution License \(CC BY\)](https://creativecommons.org/licenses/by/4.0/). The  
use, distribution or reproduction in other  
forums is permitted, provided the original  
author(s) and the copyright owner(s) are  
credited and that the original publication in this  
journal is cited, in accordance with accepted  
academic practice. No use, distribution or  
reproduction is permitted which does not  
comply with these terms.

# Comparative metagenomics at Solfatara and Pisciarelli hydrothermal systems in Italy reveal that ecological differences across substrates are not ubiquitous

Ifeoma R. Ugwuanyi<sup>1\*</sup>, Marilyn L. Fogel<sup>2</sup>, Roxane Bowden<sup>3</sup>, Andrew Steele<sup>3</sup>, Giuseppe De Natale<sup>4,5</sup>, Claudia Troise<sup>4,5</sup>, Renato Somma<sup>4,6</sup>, Monica Piochi<sup>4</sup>, Angela Mormone<sup>4</sup> and Mihaela Glamoclija<sup>1\*</sup>

<sup>1</sup>Department of Earth and Environmental Sciences, Rutgers University, Newark, NJ, United States, <sup>2</sup>EDGE Institute, University of California, Riverside, Riverside, CA, United States, <sup>3</sup>Earth and Planets Laboratory, Carnegie Institution for Science, Washington, DC, United States, <sup>4</sup>Istituto Nazionale di Geofisica e Vulcanologia, Osservatorio Vesuviano, Naples, Italy, <sup>5</sup>Consiglio Nazionale delle Ricerche INO, Naples, Italy, <sup>6</sup>Consiglio Nazionale delle Ricerche IRIS, Naples, Italy

**Introduction:** Continental hydrothermal systems (CHSs) are geochemically complex, and they support microbial communities that vary across substrates. However, our understanding of these variations across the complete range of substrates in CHS is limited because many previous studies have focused predominantly on aqueous settings.

**Methods:** Here we used metagenomes in the context of their environmental geochemistry to investigate the ecology of different substrates (i.e., water, mud and fumarolic deposits) from Solfatara and Pisciarelli.

**Results and Discussion:** Results indicate that both locations are lithologically similar with distinct fluid geochemistry. In particular, all substrates from Solfatara have similar chemistry whereas Pisciarelli substrates have varying chemistry; with water and mud from bubbling pools exhibiting high  $\text{SO}_4^{2-}$  and  $\text{NH}_4^+$  concentrations. Species alpha diversity was found to be different between locations but not across substrates, and pH was shown to be the most important driver of both diversity and microbial community composition. Based on cluster analysis, microbial community structure differed significantly between Pisciarelli substrates but not between Solfatara substrates. Pisciarelli mud pools, were dominated by (hyper)thermophilic archaea, and on average, bacteria dominated Pisciarelli fumarolic deposits and all investigated Solfatara environments. Carbon fixation and sulfur oxidation were the most important metabolic pathways fueled by volcanic outgassing at both locations. Together, results demonstrate that ecological differences across substrates are not a widespread phenomenon but specific to the system. Therefore, this study demonstrates the importance of analyzing different substrates of a CHS to understand the full range of microbial ecology to avoid biased ecological assessments.

## KEYWORDS

hydrothermal system, Solfatara, Pisciarelli, microbial diversity, metagenomics, MAGs

## Introduction

Continental hydrothermal systems (CHSs) are usually formed within diverse igneous lithologies (i.e., mafic, andesitic, and felsic) and the hydrothermal fluids derived from deep subsurface sources may be mixed with marine, brine, or meteoritic water resulting in geochemically diverse environments. These diverse environments exhibit substantial differences in the availability and abundance of electron acceptors and donors (Fournier, 1989; Shock et al., 2010; Lowenstern et al., 2015; Lindsay et al., 2018; Amenabar and Boyd, 2019), which microorganisms exploit as sources of energy (Amenabar et al., 2017; Lindsay et al., 2019; Puopolo et al., 2020; Aulitto et al., 2021).

CHSs have been the subject of many studies as they are a surface manifestation of hydrothermal activities, which are easily accessible for diverse microbiological studies (Inskeep et al., 2013; Menzel et al., 2015; Colman et al., 2016; Mardanov et al., 2018; Oliverio et al., 2018; Power et al., 2018; Boyer et al., 2020; Podar et al., 2020; Crognale et al., 2022 as a few examples). These studies have revealed that hot springs support microbial communities that are exceptionally diverse and vary in their response to physical and geochemical parameters (Inskeep et al., 2013; Sharp et al., 2014; Lindsay et al., 2018; Power et al., 2018; Colman et al., 2019a,b; Podar et al., 2020). Some studies have found pH to be the primary physical parameter that influences the microbial community composition of hot springs in Yellowstone National Park (Boyd et al., 2010; Inskeep et al., 2013; Colman et al., 2016, 2019a,b), Tengchong, China (Hou et al., 2013; Xie et al., 2015), Iceland (Moreras-Marti et al., 2021), and volcanic provinces in New Zealand (Power et al., 2018). In contrast, other studies have identified temperature as the most important driver of microbial community composition in hot springs (Miller et al., 2009; Cole et al., 2013; Sharp et al., 2014; Podar et al., 2020). Further, at Yellowstone National Park, subsurface processes including phase separation and mixing with meteoritic fluids were shown to shape the ecology of hot spring communities through their influence on the availability of nutrients that support microbial metabolism (Lindsay et al., 2018; Colman et al., 2019a). In addition to temperature, pH, phase separation and mixing of fluids, Fullerton et al. (2021) found that microbial diversity analyzed from fluids and associated sediments reflects the subsurface geological structures that fluids traverse, which in turn influences carbon cycling within the subduction zone in Costa Rica.

While we have learned a great deal about hot springs, their geochemical complexity and the observed ecological differences between water and hot spring deposits (Cole et al., 2013; Colman et al., 2016) highlight the need for studies analyzing different substrates (e.g., fumarolic deposits) to understand the full range of microbial ecology in CHSs. Some studies have analyzed microbial communities from different available substrates (Glamoclija et al., 2004; Ellis et al., 2008; Benson et al., 2011; Sharp et al., 2014; Wall et al., 2015; Medrano-Santillana et al., 2017; Crognale et al., 2018; Marlow et al., 2020; Arif et al., 2021); however, to the best of our knowledge, no CHSs study has used as many different substrates from the same hydrothermal system and correlated their environmental settings and metagenomes to characterize microbial ecology. The lack of comparison among different substrates (fumarolic deposits, water and mud from mud pools) may derive from the fact that not all substrates are present at all CHSs. In this study, we use metagenomes to investigate the microbial ecology in different substrates (i.e., water, mud and fumarolic deposits) from two CHSs in the context of their environmental geochemistry. The objectives of this study were to: (1) assess the microbial diversity

of different CHSs and a variety of available substrates (2) identify the metabolic potential of these microbial communities in connection to environmental geochemistry.

The study areas are Solfatara and Pisciarelli CHSs (Figure 1) located within Campi Flegrei Caldera (CFC); an 8 km nested caldera in Naples (Italy) formed by the Campania Ignimbrite (39 ka) and Neapolitan Yellow Tuff (15 ka) eruptions (De Natale et al., 2016; Rolandi et al., 2020a,b). Present-day activities at CFC are characterized by large-scale hydrothermal circulation, gaseous emissions, and intense ground deformation (Troise et al., 2019; Moretti et al., 2020; Chiodini et al., 2021). According to Caliro et al. (2007), fumaroles and mud pools at Solfatara and Pisciarelli are fed by fluids of mixed magmatic-meteoritic origin. The Solfatara crater is 0.6 km in diameter and maintains hydrothermal activity at fumaroles where gas emissions reach temperatures from 145°C up to 165°C, while mud pools have an average temperature of approximately 45°C (Glamoclija et al., 2004; Chiodini et al., 2011). Furthermore, the Solfatara environment is extremely acidic (mud pool: 1.9–2.1 pH and fumarolic deposits: 1.3–2.2 pH; Crognale et al., 2018). The second location, Pisciarelli, sits on the outside northeastern wall of the Solfatara crater. Pisciarelli holds an unstable fumarole field characterized by consistent deposit



FIGURE 1

Sampling points at Solfatara-Pisciarelli hydrothermal systems. (A) Location map of Solfatara-Pisciarelli hydrothermal systems on contoured map of Italy (red dot). (B) Oblique view of Solfatara and Pisciarelli systems; red dashed lines represent faults; yellow dots are sampling points (E and D stand for Solfatara mud pool and fumaroles, respectively). (C) Sampling point of Solfatara fumarolic deposits (SF) next to the main fumarole Bocca Grande. (D) Close-up view of deposits to show heterogeneity of the material in regard to grain size and mineralogy (note different colors of deposits). (E) Solfatara mud pool (SMP) with bubbling water and warm muddy substrate near the pool. (F) Overview of the Pisciarelli location with marked sampling points. (G) Pisciarelli large pool (PLP) with bubbling hot mud (temp. 84.1°C). (H) Pisciarelli fumarolic deposits (PF) with sulfur crystals precipitate. (I) Pisciarelli small pool (PSP) sampling point. (J) Pisciarelli epilithic microbial layer (PLP-E) observed and sampled on the wall near the outflow channel of the large pool.

degassing, fluid emission from ephemeral vents, and boiling mud pools. This degassing activity is episodically accompanied by seismic swarms and macroscopic morphology changes such as the appearance of vigorously degassing vents, collapsing landslides, and bubbling mud (Fedele et al., 2021). Fumarolic deposits and mud pools at Pisciarelli are also very acidic (pH: 0.5–3) and temperatures of fumaroles ranges from 95°C to 110°C, while mud pools have temperatures between 84°C and 95°C (Ciniglia, 2005; Troiano et al., 2014; Poichi et al., 2019). In Solfatara-Pisciarelli CHSs, the major gases in fumarole vents are H<sub>2</sub>O and CO<sub>2</sub> while the minor gases include H<sub>2</sub>S, N<sub>2</sub>, H<sub>2</sub>, CH<sub>4</sub>, He, Ar, and CO (Chiodini et al., 2010; Aiuppa et al., 2013). In both systems, fumaroles have a similar content of H<sub>2</sub>O, CO<sub>2</sub>, Ar, He, and N<sub>2</sub>, however, they differ in their concentration of H<sub>2</sub>S, H<sub>2</sub>, and CO (Chiodini et al., 2001). Solfatara and Pisciarelli also differ in their fluid geochemistry; fluid in mud pools of Pisciarelli have been reported to have higher NH<sub>4</sub><sup>+</sup> concentrations (508–1,026 mg L<sup>-1</sup>) compared to Solfatara (<1 mg L<sup>-1</sup>; Martini et al., 1991; Valentino and Stanzione, 2003; Glamoclija et al., 2004; Poichi et al., 2019) resulting in the precipitation of the minerals mascagnite [(NH<sub>4</sub>)<sub>2</sub>SO<sub>4</sub>] and tschermigite [(NH<sub>4</sub>)Al(SO<sub>4</sub>)<sub>2</sub>·12(H<sub>2</sub>O)] (Poichi et al., 2019). The geochemical diversity of substrates in Solfatara-Pisciarelli CHSs provides an excellent location for evaluating the composition, structure, and functional potential of thermophilic microorganisms in different hydrothermal substrates and locations.

## Materials and methods

To investigate the near-surface microbial community composition, structure and function at two CHSs, water, mud, and fumarolic deposits samples were collected from Solfatara and Pisciarelli (Figures 1A,B), in October 2012 (Supplementary Method). All samples were collected in triplicates, aseptically, using sterile Falcon tubes, Nalgene bottles, scoops, and gloves. After the collection, the samples were stored at –20°C until further processing; samples for long term storage were stored at –80°C. Temperature, pH, and redox potential (Eh) were measured *in situ* using a portable probe (Table 1). Gas readings were taken from the continuous Istituto Nazionale di Geofisica e Vulcanologia (INGV) gas monitoring station at Solfatara and Pisciarelli (Table 1).

## Geochemical characterization

About 1 g of solid sample (fumarolic deposits and mud) was added to 20 ml of MilliQ water and extracted as described in Lezcano et al. (2019). The concentration of water-soluble anions (F<sup>-</sup>, Cl<sup>-</sup>, NO<sub>2</sub><sup>-</sup>, Br<sup>-</sup>, NO<sub>3</sub><sup>-</sup>, PO<sub>4</sub><sup>3-</sup>, and SO<sub>4</sub><sup>2-</sup>) in extracts and water samples was measured in triplicate using an 881 compact IC pro ion chromatography system (Metrohm, Switzerland) with a Metrosep A Supp 5-250/4.0 column. The concentration of NH<sub>4</sub><sup>+</sup> in extracts and water samples was measured using the alkaline hypochlorite/phenol nitroprusside method, after adding sodium citrate to prevent the precipitation of calcium and magnesium salts (Solorzano, 1969). Before measuring concentrations of NH<sub>4</sub><sup>+</sup> in water samples, samples were diluted 10-fold. Ammonium sulfate (NH<sub>4</sub>)<sub>2</sub>SO<sub>4</sub> solutions (0, 660, 1,320, 3,300, 6,600, and 13,200 ppm) were prepared and used as standard. The absorbance of each sample was measured in triplicate using an Evolution 60S UV-Vis Spectrophotometer at 640 nm wavelength.

X-ray fluorescence (XRF) was used to examine the chemical composition of mud and fumarolic deposits samples. Samples were analyzed in triplicate using a Horiba XGT-1000WR X-ray Fluorescence with an Rh tube X-ray source and elemental wt.% was determined using the XGT-1000WR software's quantification (Supplementary Method).

## Stable isotopic analysis of carbon, nitrogen, and sulfur

Carbon, nitrogen, and sulfur stable isotope and elemental concentration analyses were performed at the Earth and Planets Laboratory, Carnegie Institution for Science. For organic carbon (TOC), and organic δ<sup>13</sup>C measurements, samples were weighed into silver boats and fumed with 12 N HCl for 12–14 h. δ<sup>13</sup>C and δ<sup>15</sup>N isotopes were measured using a Thermo Scientific Delta VPlus isotope ratio gas-source mass spectrometer connected to a Carlo Erba (NA 2500) elemental analyzer (EA/IRMS) via a ConFlo III interface. δ<sup>34</sup>S was analyzed by the same gas-source mass spectrometer but connected to an Elementar Americas vario Micro CUBE elemental analyzer (EA-IRMS) via a ConFlo III interface. Stable isotope values are reported in standard delta notation as ‰ variations relative to: Pee Dee Belemnite (PDB) for δ<sup>13</sup>C, atmospheric N<sub>2</sub> gas (AIR) for δ<sup>15</sup>N,

TABLE 1 Field measurements for water (W), mud (M), mud outlet (MO), epilith from dry mud wall (E), and fumarolic deposits (D) samples collected from Solfatara-Pisciarelli hydrothermal systems.

Location	Sample	T (°C)	pH	Eh (mV)	CO <sub>2</sub> (%)	CH <sub>4</sub> (ppm)	He (ppm)	H <sub>2</sub> (ppm)	N <sub>2</sub> (ppm)	Ar (ppm)	H <sub>2</sub> S (ppm)
Pisciarelli	PLP	84.1	2.5	-485							
	PLP-MO	78.9	2.5	-486							
	PLP-E	74	-	-501	98.43	259	9	870.28	7,686	110	4,496
	PSP	88.8	1.5	-628							
	PSP-M	94.6	2	-622							
	PF-D	93.3	1.5	-622							
Solfatara	SMP-W	42.5	1	330							
	SMP-M	68.8	1	330	24.1	13	2.35	490	469	0.39	1,250
	SF-D	88.7	1	198							

The gas readings were taken close to the fumarolic emission sites; at Solfatara, the gas monitoring station was near our sampling site for SF-S, and at Pisciarelli, near sampling site for PF-S2. Pisciarelli large pool (PLP), Pisciarelli small pool (PSP), Pisciarelli fumarole (PF), Solfatara mud pool (SMP), and Solfatara fumarole (SF).



Vienna Canyon Diablo Troctolite (V-CDT) for  $\delta^{34}\text{S}$ , and with an analytical error of  $\pm 0.1\%$ . In-house  $\delta^{13}\text{C}$  and  $\delta^{15}\text{N}$  standards were also used and calibrated against international and certified standards as well. Additional  $\delta^{34}\text{S}$  standards include the International Atomic Energy Agency reference materials IAEA-S-1 ( $\delta^{34}\text{S} = -0.3\%$ ), and IAEA S3 ( $\delta^{34}\text{S} = -32.3\%$ ), as well as NBS-123 ( $\delta^{34}\text{S} = -17.09\%$ ), NBS-127 ( $\delta^{34}\text{S} = -21.17\%$ ), and USGS-42 ( $\delta^{34}\text{S} = -7.84\%$ ). A subset of the samples was analyzed in 2021 at the EDGE Stable Isotope Laboratory at the University of California Riverside to confirm the very negative nitrogen isotope values in some of these samples. USGS25 ( $\delta^{15}\text{N} = -30.41\%$ ) and USGS40 ( $\delta^{15}\text{N} = -4.52\%$ ) were used as two of our calibrating standards and confirmed the values measured earlier at the Earth and Planets Laboratory.

## DNA extraction, metagenomic sequencing and sequence processing

About 0.25 g of mud and fumarolic deposits was used for DNA extraction. Before DNA extraction, fumarolic deposits were powdered using a sterilized agate mortar and pestle. Water samples were filtered in the laboratory using a 0.2  $\mu\text{m}$  VWR black polycarbonate filter. Filters were cut into small pieces with a sterile scalpel and used for DNA extraction. DNA was extracted using DNeasy PowerSoil kit (Qiagen Inc., Valencia, CA, United States) with modifications to the manufacturer's instructions (Supplementary Method) and were stored at  $-80^\circ\text{C}$  until further processing. Sequencing libraries were prepared using the Accel-NGS 2S Plus DNA Library Kit (Swift Biosciences Inc., Ann Arbor, MI, United States) according to the manufacturer's protocols. The prepared library was sequenced on the Illumina Novaseq platform at the Oklahoma Medical Research Foundation. Metagenome sequence quality was assessed using FastQC v0.11.5<sup>1</sup> and reads with a mean quality score less than 25 were discarded. Sequences were quality trimmed and Illumina sequencing adapters removed using Trimmomatic v0.36 (Bolger et al., 2014) with the following parameters: SLIDINGWINDOW:4:15, LEADING:3, TRAILING:3, and MINLEN:36. After quality control, taxonomic annotation of metagenomes was performed using Kaiju v1.8.2 (Menzel et al., 2016) against the NCBI nr + euk database (accessed on February 16, 2022) with the following parameters (run mode: greedy, minimum match length: 11, minimum match score: 75, allowed mismatches: 5). To compare the effects of taxonomic profiling using metagenome vs. 16S rRNA gene sequences, the trimmed metagenome sequences were uploaded to the MG-RAST online server (Meyer et al., 2008) and then passed through the MG-RAST QC pipeline. Following the quality control on MG-RAST, 16S rRNA gene sequences present in the metagenome (metagenome-derived 16S rRNA gene sequences) were identified and taxonomy assigned. Taxonomic classification of the metagenome-derived 16S rRNA gene sequences was done using the Greengenes rRNA database (DeSantis et al., 2006) hosted in MG-RAST with a minimum cut-off identity of 60% and e-value of 5. Since contamination leads to an overestimation of diversity, especially in low biomass samples like that of Solfatara and Pisciarelli (Karstens et al., 2019), after assigning taxonomy, we removed molecular biology kit and laboratory contaminants (which hereinafter are referred to as "kitome"), low

abundance taxa ( $<0.01\%$ ) and sequences that were unclassified at the domain level from the taxonomy table before performing downstream analyses (Supplementary Method).

## Co-assembly, metagenomic binning, and MAG quality assessment

Bins were generated from 10 Solfatara and 17 Pisciarelli metagenomes. To maximize genome recovery, we co-assembled several samples based on their taxonomic composition. All 10 Solfatara metagenomes were co-assembled and all 17 Pisciarelli metagenomes were co-assembled using MEGAHIT v1.2.9 (Li et al., 2015). Contigs longer than 1,000 bp were then binned using the metaWRAP binning module (Uritskiy et al., 2018) which incorporates three binning methods: CONCOCT v1.1.0 (Alneberg et al., 2014), MaxBin2 v2.2.6 (Wu et al., 2016), and metaBAT2 v2.12.1 (Kang et al., 2019). The metaWRAP refinement module (Uritskiy et al., 2018) was used to merge results from the three binning methods using the  $-c$  50 and  $-x$  10 options to obtain bins with over 50% completeness and less than 10% contamination according to the CheckM tool v1.0.12 (Parks et al., 2015). Bins with  $>50\%$  completeness and  $<10\%$  contamination were then reassembled with SPAdes v3.13.0 (Bankevich et al., 2012) to improve the assembly quality. The contamination and completeness of resulting Metagenome Assembled Genomes (MAGs) were reassessed with CheckM (Parks et al., 2015).

## Taxonomic and functional annotation of MAGs

Taxonomy was assigned to MAGs using GTDB-TK v1.7.0 (Chaumeil et al., 2020). To assess whether MAGs belong to the same species (species ANI  $\geq 95\%$ ), average nucleotide identity (ANI) was calculated for each possible pair of MAGs using FastANI v1.33 (Jain et al., 2018). MAGs with taxonomic assignment similar to previously identified kitome (e.g., *Corynebacterium* and *Staphylococcus*; Sheik et al., 2018; Weyrich et al., 2019) were not included in downstream analyses. Functional annotation of MAGs, including gene prediction was done using Prokka v1.14.5 (Seemann, 2014). Predicted genes were compared against the Kyoto Encyclopedia of Genes and Genomes (KEGG) database using BlastKOALA server (Kanehisa et al., 2016) to obtain KEGG Orthology (KO) annotations.

## Abundance of MAGs in metagenomes

To assess the abundance of recovered MAGs, quality trimmed sequences from each metagenome were mapped against each MAG using BMap v38.96. Sequence counts were normalized as the number of sequences recruited per kilobase of MAG and gigabase of metagenome (RPKG). The normalized sequence counts allowed for direct comparison of genome abundance between metagenome of different depths.

## Statistical analyses

All statistical analyses were performed in R v4.0.2 (R Core Team, 2020). Principal Component Analysis (PCA) was performed with

1 <https://www.bioinformatics.babraham.ac.uk/projects/fastqc/>


environmental parameters using the “*prcomp*” function in the *stat* package with scaling enabled. PCA results were graphed using the “*ggbiplot*” function from the *ggbiplot* v0.55 package. Before using the geochemical data for statistical analyses, variables below detection limit in all samples were excluded and the dataset transformed using z-score. After removing kitome and all potential contaminants, we calculated alpha diversity using the species abundance table obtained from metagenome-derived 16S rRNA gene (Greengenes) and metagenome (NCBI nr + euk) taxonomic assignment. Alpha diversity (Shannon, observed richness and Pielou’s evenness) was calculated using the “*estimate\_richness*” function from the *phyloseq* v1.32.0 package in R. Nonpareil v3.0 (Rodriguez-R et al., 2018) was then used to estimate coverage and also calculate diversity with kmer kernel and default parameters. Kruskal-Wallis test was used to investigate whether alpha diversity varied significantly between locations and substrates. The “*lm()*” function in R was used to perform linear regression to evaluate potential effects of environmental variables on alpha diversity. Bray–Curtis dissimilarity based on genus and species abundance was used to determine differences in microbial community composition. The Bray–Curtis distance calculated was visualized using a Non-metric Multidimensional Scaling (NMDS) plot. Analysis of Similarity (ANOSIM) was performed on the Bray–Curtis dissimilarity matrix using the *vegan* v2.5-6 package to evaluate the significance of microbial compositional differences between the two locations and different types of substrates. Similarity Percentage (SIMPER) analysis was performed using the *vegan* v2.5-6 package to identify genera that contributed to the dissimilarity between two locations and different types of substrates. Mantel test using Spearman’s correlation coefficient with 999 permutations was performed to evaluate the significance of correlation between community composition (Bray–Curtis dissimilarity) and environmental parameters (Euclidean distance).

## Results and discussion

### Geochemical context of Solfatara-Pisciarelli hydrothermal systems

At Solfatara-Pisciarelli CHSs (Figure 1), the crater structure that forms the rock substrate (alkaline potassic tephra and lava ranging from trachybasalt to phonotrachyte) for both locations was produced and shaped by the same volcanic events (Piochi et al., 2015). Solid substrates from both locations have similar bulk elemental composition [Supplementary Figure 1; Supplementary Table 1 and Piochi et al. (2014), Piochi et al. (2015)]. In addition, the same magma chamber provides a heat source for the fumaroles and mud pools (Chiodini et al., 2001; Valentino and Stanzione, 2003) of both systems. However, tectonic features diverge the fluids that feed Pisciarelli mud pools to pass through old marine sediments with strong organic imprints where the fluids become enriched in  $\text{NH}_4^+$  (Piochi et al., 2019).

PCA based on temperature, pH, Eh, and water-soluble nutrients showed further distinction between Solfatara and Pisciarelli (Figure 2; Supplementary Table 2). Pisciarelli an extremely acidic (pH: 1.5–2.5) and reducing (Eh: –628 to –485) environment has higher temperatures (74°C to 95°C) and gas concentrations including  $\text{H}_2\text{S}$  and  $\text{CH}_4$  (Table 1) compared to Solfatara (pH: ~1; temperature: 42°C to 88.7°C; Eh: 198 and 330 mV), making Pisciarelli a more active and extreme hydrothermal environment than Solfatara. These higher temperatures, which inhibit the solubility of oxygen (Boyer et al., 2020), together with



higher concentrations of reducing gases may contribute to the more reducing conditions we observed at Pisciarelli. The  $\text{H}_2\text{S}$  gas released in CHSs may be oxidized abiotically by oxygenated meteoritic waters (Nordstrom et al., 2005, 2009) or biotically by chemosynthetic microorganisms leading to the higher concentration of  $\text{SO}_4^{2-}$  we observed in mud pools (Pisciarelli: 3,326–6,208 ppm; Solfatara: 206–2,888 ppm) compared to fumarolic deposits (Pisciarelli: 118–439 ppm; Solfatara: 567–610 ppm). The concentrations of  $\text{SO}_4^{2-}$  in Pisciarelli mud pools were two times that of Solfatara mud pool possibly due to the higher concentration of  $\text{H}_2\text{S}$  gas measured at Pisciarelli. The concentration of  $\text{NH}_4^+$  was also higher in mud pools, particularly in Pisciarelli mud pools (Pisciarelli: 1,130–1,998 ppm; Solfatara: 1.1–36 ppm) than in fumarolic deposits (Pisciarelli: 0.8 to 38 ppm; Solfatara: 0.3 ppm) which corresponds with other studies that report higher concentrations of  $\text{NH}_4^+$  in Pisciarelli mud pools (Martini et al., 1991; Valentino and Stanzione, 2003; Glamoclija et al., 2004; Poichi et al., 2019). Temperature and geochemical measurements from Pisciarelli large mud pool revealed an environmental gradient; values were lower at the discharge channel (temperature: 79°C;  $\text{SO}_4^{2-}$ : 134.4–193.6 ppm;  $\text{NH}_4^+$ : 46.5–67.8 ppm) compared to the main bubbling pool (temperature: 84°C;  $\text{SO}_4^{2-}$ : 3326–6,208 ppm;  $\text{NH}_4^+$ : 1,130–1,998 ppm). The low concentrations of  $\text{SO}_4^{2-}$  and  $\text{NH}_4^+$  along the discharge channel may result from the removal of  $\text{H}_2\text{S}$  and  $\text{NH}_4^+$  possibly due to oxidation and volatilization as fluid flows into the channel.

### Discrepancies between metagenome-derived 16S rRNA gene and metagenomic profiles

In this study, a total of 7 Solfatara and 10 Pisciarelli samples were analyzed. Solfatara samples had between 54,932,932 to 210,855,916 (average = 126,261,781) quality filtered metagenome sequences whereas Pisciarelli had between 119,199,732 to 230,316,988 (average = 179,177,105) quality filtered metagenome sequences. We compared taxonomic profiles generated from metagenome against metagenome-derived 16S rRNA gene sequences and observed that metagenome sequences identified more taxa than metagenome-derived


16S rRNA gene sequences, which corresponds to other studies that detected an increased number of taxa with whole genome shotgun sequencing compared to the 16S amplicon method (Ranjan et al., 2016; Brumfield et al., 2020). For example, Ranjan et al. (2016) reported that with the same number of sequences, whole genome shotgun sequencing identified twice as many species as the 16S method. We observed that metagenome sequences identified 56 phyla while metagenome-derived 16S rRNA gene sequences identified 26 phyla. Only 3 out of the 26 phyla detected by metagenome-derived 16S rRNA gene profiling were not detected by metagenomic profiling. Metagenomic profiling, on the other hand, identified 35 phyla not identified by metagenome-derived 16S rRNA gene profiling with 12 of them being viral and eukaryotic phyla. Overall, the dominant bacterial and archaeal phyla detected were similar irrespective of profiling method. Predominant bacterial and archaeal phyla detected by both profiling methods include *Crenarchaeota*, *Proteobacteria*, *Firmicutes*, and *Actinobacteria* (Figures 3A,B). At the genus level, metagenomic profiling also identified more genera than metagenome-derived 16S rRNA gene profiling (Figures 4A,B). Of the 245 genera identified across all samples by metagenomic profiling methods only 48 genera (20%) were identified with both profiling methods. Metagenomic profiling identified 197 genera not identified by metagenome-derived 16S rRNA gene profiling including *Acidilobus*, *Acidibacillus*, *Thermogymnomonas*, *Ampullavirus*, and *Bicaudavirus* while genera including *Acetobacterium* and *Caldococcus* were unique to metagenome-derived 16S rRNA gene profiling. We observed that both methods identified dominant genera including *Acidianus*, *Pyrobaculum*, and *Sulfobacillus*.

Next, we analyzed the effect of both taxonomic profiling methods on diversity (Shannon diversity, observed richness, Pielou's evenness). Before calculating the diversity, we identified and removed kitome


(Supplementary Figure 3; Supplementary Tables 4, 5), low abundance taxa and sequences that were unclassified at the domain level from the taxonomy table to avoid an overestimation of diversity and a misrepresentation of community composition (Karstens et al., 2019). Our results showed that Shannon diversity and observed richness were consistently higher when the taxonomy table from metagenomic profiling was used as input compared to when we used the taxonomy table from metagenome-derived 16S rRNA gene profiling (Figures 5A,B). Overall, our results reflect that the 16S amplicon approach, which has been the most employed approach for studying CHSS' microbiome, identifies a significantly lower number of bacterial species and completely excludes viruses and fungi which is similar to reports from other studies (Ranjan et al., 2016; Brumfield et al., 2020). Although metagenome sequencing permits the identification of more taxa, the choice between 16S rRNA gene and metagenome sequencing ultimately depends on the ecological questions and objectives of any given study. Since metagenome sequences encompass all members of the microbiome and provide high-resolution diversity analysis, which agrees with our objective to understand the full range of microbial ecology in available substrates from Solfatara-Pisciarelli CHSS, the further analyses and results hereinafter are based on the taxonomy table generated from metagenomic profiling.

### Microbial diversity of Solfatara-Pisciarelli hydrothermal systems

Shannon diversity in Solfatara-Pisciarelli CHSS ranged from 1.20 to 4.26 (Figure 5B; Supplementary Table 8). We observed significant variations in Shannon diversity (Kruskal-Wallis:  $p < 0.05$ ) between









Solfatara and Pisciarelli which were supported by Nonpareil diversity values (Supplementary Figure 4; Supplementary Table 8); on average, Shannon diversity was lower at Pisciarelli (Shannon: 1.20–3.52) than at Solfatara (Shannon: 3.55–4.26). Additionally, microbial communities were more uneven (Kruskal–Wallis:  $p < 0.05$ ) at Pisciarelli (Pielou's evenness: 0.26–0.74) than at Solfatara (Pielou's evenness: 0.67–0.84). However, there was no significant difference in observed richness between these locations (Solfatara: 114–201 species; Pisciarelli: 102–166 species; Kruskal–Wallis:  $p = 0.24$ ). The decreased Shannon diversity at Pisciarelli may have resulted from the combined effects of reducing conditions, extremely low pH, and high temperature. The addition of highly reducing conditions at Pisciarelli to an already extreme environment (high temperature and low pH) may cause further selection against certain microbial groups by hindering their growth and metabolism, thus leading to the lower Shannon diversity observed (Kimbrough et al., 2006; Seo and DeLaune, 2010; Husson, 2013; Zhang et al., 2015). Alpha diversity in substrates showed some variation (e.g., on average, mud and fumarolic deposits had higher Shannon diversity than water, and richness showed less variability in water and mud); however, these differences were not statistically significant (Kruskal–Wallis, Shannon:  $p = 0.97$ ; Pielou's evenness:  $p = 0.83$ ; observed genus richness:  $p = 0.09$ ) even when substrates were analyzed separately for each location which implies that species alpha diversity does not differ across substrates in the Solfatara–Pisciarelli CHSs. This result contrast with other studies comparing microbial diversity in water and solid substrates from hot springs, which showed differences in richness (Colman et al., 2016) and evenness (Cole et al., 2013) across substrates.

A comparison of diversity and physical parameters showed pH (Shannon:  $R^2 = 0.73$ ; Nonpareil:  $R^2 = 0.43$ ,  $p < 0.05$ ) to be the primary driver of microbial diversity which is consistent with several studies that report pH as the major predictor of microbial diversity in some


hydrothermal systems (Oliverio et al., 2018; Power et al., 2018). Results also showed that Eh had a significant correlation (Shannon:  $R^2 = 0.62$ ; Nonpareil:  $R^2 = 0.43$ ,  $p < 0.05$ ) with diversity. Temperature on the other hand had minimal effect on diversity (Shannon:  $R^2 = 0.12$ ,  $p = 0.09$ ; Nonpareil:  $R^2 = 0.02$ ,  $p = 0.25$ ). This is in contrast to previous studies that reported a strong relationship between temperature and microbial diversity in hot springs (Miller et al., 2009; Sharp et al., 2014). Comparably, minimal effect of temperature on alpha diversity has been reported for hot spring communities in Yellowstone, United States, Fludir, Iceland and Tibetan Plateau, China (Wang et al., 2013; Podar et al., 2020).

## Microbial community composition of Solfatara–Pisciarelli hydrothermal systems

After removing kitome and all potential contaminants, a total of 490 species (245 genera) were identified across all samples corresponding to 11 archaeal, 31 bacterial, 10 eukaryotic, and four viral phyla (Supplementary Table 6). Our results showed that overall, 33% (133) of the species detected were shared across the different types of substrates but each substrate contained unique species among which water had the least number of unique taxa and mud contained the highest (Figure 6B). NMDS plot (Figure 7) generated based on Bray–Curtis dissimilarity matrix revealed that the microbial community structure of Pisciarelli was distinct from Solfatara (ANOSIM:  $R = 0.63$  for species;  $R = 0.67$  for genus,  $p < 0.05$ ). On average, the most abundant phylum at Pisciarelli was *Crenarchaeota* (46%) followed by *Proteobacteria* (5%) and *Actinobacteria* (2%), whereas Solfatara was dominated by *Firmicutes* (23%), *Proteobacteria* (21%), and *Actinobacteria* (12%; Figure 3B). In addition, Pisciarelli substrates had a higher number of viral sequences



(4–49%) than Solfatara (1–4%; Supplementary Figure 2). Interestingly, we detected *Cyanobacteria* (0.5 to 4%) especially at Solfatara even in samples (SF-D\_and SF-D\_b) with a temperature (89°C) that exceeds the



known temperature limit for photosynthesis in acidic environments (Brock, 1985; Cox et al., 2011; Hamilton et al., 2012). The *Cyanobacteria* we detected may have been introduced into the hydrothermal system from surrounding cooler environments (by wind or fluid circulations). However, we cannot decipher with certainty if they were environmentally introduced or if they are true members of the Solfatara-Pisciarelli hydrothermal community. We observed that at the species level, both locations shared 171 species (35%), however, there were over 100 species unique to each location (Figure 6A). Species unique to Pisciarelli include thermophiles such as *Pyrolobus fumarii*, *Pyrobaculum aerophilum* and *Metallosphaera sedula*. Unique species identified at Solfatara include *Thermaerobacter* sp. FW80, *Methylacidiphilum kamchatkense* and *Ilumatobacter coccineus*.

Our results showed that the microbial community structure in the high temperature environments (74–95°C) of Pisciarelli was different. The source of Pisciarelli large mud pool (84°C) was dominated by *Acidianus* (21–68%), *Pyrobaculum* (11–21%) and *Bicaudavirus* (11–43%) but as temperature decreased away from the source (79°C), we detected a decrease in the abundance of *Acidianus* (20–23%) and *Bicaudavirus* (15–17%) but an increase in the abundance of *Pyrobaculum* (30–43%) in the discharge channel. Water from Pisciarelli small mud pool (89°C) was also dominated by *Acidianus* (48–59%), but *Pyrobaculum* accounted for <1% of total sequences in this mud pool. Interestingly, the viral genus, *Ampullavirus* accounted for over 80% of sequences in Pisciarelli epilithic microbial layer (74°C) and for 26% of sequences in both Pisciarelli fumarolic deposit (93°C) and mud from Pisciarelli small mud pool (88°C). Most of the viruses detected in Pisciarelli fumarolic deposits, epilithic microbial layer and mud from the small mud pool were known archaeal viruses (e.g., *Ampullavirus*, *Bicaudavirus*, and *Betalipothrixvirus*) even though archaea accounted for <3% of the total sequences in these samples. This difference in relative abundance between archaeal viruses and their known host suggests that each archaeal species may host more than one virus type or the archaeal viruses present in Solfatara-Pisciarelli CHSs may have a




broader host range that includes bacteria or/and eukaryotes (Munson-McGee et al., 2018). When substrates were compared at each location, we observed that Pisciarelli substrates harbored significantly different (ANOSIM species:  $R=0.64$ ; genus:  $R=0.62$ ,  $p<0.05$ ) microbial communities. SIMPER analysis showed that the sulfur-oxidizing archaeal genus *Acidianus* was significantly ( $p<0.05$ ) more abundant in Pisciarelli water communities, the archaeal genus *Pyrobaculum* showed a higher relative abundance in mud communities, and *Ampullavirus* showed a higher relative abundance in fumarole deposits communities (Supplementary Table 9; Figure 4B). Overall, Pisciarelli water and mud communities were similar but distinct from communities in Pisciarelli fumarolic deposits. The distinction between communities in the mud pools and fumarolic deposits at Pisciarelli may be linked to fluids and/or may reflect the availability of oxygen. Although the entire Pisciarelli environment has high temperatures and is highly reducing, the vigorous mixing of hydrothermal gas with air may create pockets of atmospheric  $O_2$  in pore spaces of fumarolic deposits which support aerobic communities that may be absent or in low abundance in mud pools. In contrast, high temperatures of mud pools inhibit the dissolution of oxygen thereby creating microaerobic environments that may favor thermophilic facultative and obligate anaerobes such as *Acidianus* and *Pyrobaculum*. Furthermore, the presence of *Pyrobaculum* specifically *Pyrobaculum arsenaticum* which is a strict anaerobe (Huber et al., 2000) and members of the genus *Sulfuracidifex* who are all obligate aerobes in Pisciarelli large pool may be an indication that conditions in this pool fluctuate between microaerobic and completely anaerobic, possibly in congruence with the intensity of hydrothermal activity.

At Solfatara, we observed variability in genus abundance across samples even between replicates (Figure 4B). For example, *Acidibacillus* accounted for 11% of sequences in SMP-M\_a1 but was <1% in replicate mud sample, SMP-M\_b. The difference between replicates may derive from the heterogeneous nature of Solfatara-Pisciarelli CHSs; however, seeing that genus abundance also varied in our sequencing replicates (SMP-M\_a1 and SMP-M\_a1.2), the variability in genus abundance may likely be bias introduced from sequencing. Results also showed that a large percentage of Solfatara sequences (20–36%) were unclassified at the genus level, suggesting a considerable amount of potentially novel genera at this environment. Interestingly, at Solfatara, we detected several genera that are not known thermophiles and not commonly found at  $pH<2$  (e.g., *Rhizopus*; 1.7–14%, *Actinomadura*; 1–9%, *Terasakiella*; 0.7–5.6%, and *Clostridioides*; 0.3–2.5%; Wang et al., 2014; Strazzulli et al., 2020). These genera were present in Solfatara water (43°C), mud (69°C), and fumarolic deposits (89°C). Furthermore, we detected these genera in most Pisciarelli samples but to a lesser degree. These microorganisms may not be native to the hydrothermal systems but likely introduced into the habitat from extensive human activity around the crater. In addition, the fluids in mud pools are a mixture of hydrothermal fluids and meteoric water which could deliver genetic material from non-native microorganisms to the hydrothermal systems. This possible introduction of non-native microorganisms into CHSs may be a potential problem for microbial ecology studies since the very nature of the CHSs makes it difficult to completely exclude all environmental contaminants. In contrast to Solfatara water and fumarolic deposits communities, Solfatara mud communities was dominated by *Sulfobacillus* (10–34%) and *Acidibacillus* (4–20%). However, unlike Pisciarelli, the differences across Solfatara substrates were not significant (ANOSIM species:  $R=0.03$ ,  $p=0.50$ ; genus:  $R=0.03$ ,  $p=0.43$ ) suggesting that variations in microbial community structure across substrates is not a general phenomenon but is specific to

hydrothermal systems and possibly linked to the physical and geochemical conditions of individual systems (Wang et al., 2014). The microbial community structure observed in our study is in contrast with studies that investigated the microbial ecology of Solfatara-Pisciarelli CHSs and identified *Acidithiobacillus* and *Metallosphaera* as the dominant genus in Solfatara and Pisciarelli, respectively (Iacono et al., 2020; Strazzulli et al., 2020). Furthermore, the dominance of archaea which we observed in Pisciarelli mud pools is in contrast with a study that reported a low archaea/bacteria ratio in high temperature waters (>85°C) of Pisciarelli (Crognale et al., 2022). This contrast between our study and other Solfatara-Pisciarelli studies is likely the consequence of a microbial diversity that reflects differences in sampling year/periods from active CHSs with variable geochemistry. Additionally, the dissimilarity may be related to differences in sampling points (10 cm depth vs. 1 cm depth), sample handling, DNA extraction protocol, bias introduced by 16S rRNA gene primers or sequencing technology. An assessment of the effects of environmental variables on microbial community composition showed that pH and Eh (Mantel:  $\rho=0.53$  and  $\rho=0.47$ , respectively,  $p<0.05$ ) had the strongest correlation to beta diversity which is consistent with reports from other studies that pH and redox potential shape microbial community composition (Alsop et al., 2014; Power et al., 2018). The concentrations of  $NH_4^+$  and  $SO_4^{2-}$  (Mantel:  $\rho=0.38$  and  $\rho=0.23$ , respectively,  $p<0.05$ ) also had significant correlations to beta diversity. However, temperature had no significant (Mantel:  $\rho=0.1$ ,  $p=0.14$ ) effect on the microbial community composition of Solfatara-Pisciarelli CHSs, which coincides with temperature trends observed for alpha diversity.

## Diversity, abundance and metabolic potential of Solfatara-Pisciarelli MAGs

To identify the metabolic potential of members of the microbial community and their connection to geochemistry, we generated MAGs. After co-assembly and binning, a total of 22 MAGs (10 from Solfatara and 12 from Pisciarelli) with >50% completeness and <10% contamination were recovered. Out of the 22 MAGs recovered, 16 had completeness >90% and contamination <5%. Taxonomic classification revealed that MAGs belonged to three bacterial (*Firmicutes*, *Proteobacteria*, and *Aquificota*) and 2 archaeal (*Thermoproteota* also known as *Crenarchaeota* and *Thermoplasmata*) phyla (Supplementary Tables 10, 11), with over 40% (9 out of 22) of unclassified genomes at the genus level suggesting that our MAGs represent novel genera. MAGs belonging to the phylum *Thermoproteota* were most represented in Pisciarelli water and mud while *Firmicutes* were more abundant in all Solfatara substrates and Pisciarelli fumarolic deposits (Figure 8A), which is consistent with our results from metagenome fragments. On average, the most abundant MAGs in Pisciarelli water and mud belong to species of the *Acidianus* and *Pyrobaculum* genera and an unknown species of the family *Sulfolobaceae* whereas the most abundant MAGs in fumarolic deposits belong to 2 unknown species: one species of the *Alicyclobacillaceae* family and the other species of the *Alicyclobacillales* order and a third species belonging to the *Acidianus* genus (Supplementary Table 11). In contrast, the most abundant MAG in all Solfatara samples belong to species of the *Acidianus* genus. When MAGs were dereplicated based on FastANI of  $\geq 95\%$  we found that only 2 species (*Acidianus infernus*; and an unknown species of the *Alicyclobacillaceae* family) were shared between locations further confirming that although an overlap exists between both




locations; they have different microbial community structures. Since acidic hydrothermal environments are dominated by chemolithoautotrophic communities that derive energy from inorganic compounds, we analyzed MAGs for marker genes involved in carbon fixation, sulfur, nitrogen, and methane metabolism.

### Carbon Metabolism

Organic and inorganic carbon isotope (wt% and  $\delta^{13}\text{C}$ ) values (Figures 9A,C) were very similar indicating that carbon measured at both locations is mostly organic and falls within the range typical for microorganisms with varied carbon fixation pathways (Sharp, 2007; Havig et al., 2011), which is also indicated by the functional potential of our MAGs. Genes encoding the key enzymes for Calvin-Benson-Bassham (CBB) cycle, ribulose-biphosphate carboxylase (*rbc*) and phosphoribulokinase (*prk*) were found in *Firmicutes* MAGs (*Sulfobacillus* and *R501*) as well as *Gammaproteobacteria* MAG (*Acidithiobacillus*; Supplementary Table 12; Figure 8B) similar to what has been reported in other studies (Caldwell et al., 2007; Cerqueira et al., 2018). Owing to the abundance of *Firmicutes* in Pisciarelli fumarolic

deposits and Solfatar microbial communities, CBB may be the primary mode of carbon fixation in these environments. The *rbc* gene was also detected in an archaeal MAG (*Desulfurococcus*); however, in archaea, this gene encodes enzymes reported to be involved in the reductive hexulose-phosphate pathway (Kono et al., 2017). The marker gene encoding 4-hydroxybutyryl-CoA dehydratase (*abfD*), an enzyme in 3-hydroxypropionate/4-hydroxybutyrate (3-HP/4-HB) cycle, was present in all MAGs of the *Sulfobacillaceae* family (*Acidianus*, *Metallosphaera*, *Sulfuracidifex*) which is consistent with the presence of the 3-HP/4-HB cycle in the crenarchaeal order *Sulfolobales* (Berg et al., 2010). *Crenarchaeota* especially the order *Sulfolobales* were abundant in Pisciarelli water and mud; hence, 3-HP/4-HB cycle may be the primary mode of carbon fixation in Pisciarelli mud pools. The *abfD* gene was also detected in one *Firmicutes* MAG (unknown species of the *Sulfobacillaceae* family) from Solfatar. The 3-HP/4-HB cycle to the best of our knowledge has not been reported in *Sulfobacillaceae* and the absence of other genes encoding enzymes involved in the 3-HP/4-HB cycle implies that this cycle may be absent in this *Sulfobacillaceae* MAG. One possible explanation is that the enzyme encoded by the *abfD*



gene in this *Sulfobacillaceae* MAG may be involved in an alternative metabolic pathway like has been reported for *Clostridium* (Scherf and Buckel, 1993; Scherf et al., 1994). Another possible explanation is that the *Sulfobacillaceae* MAG may have acquired the *abfD* gene via horizontal gene transfer.

Genes encoding the key enzymes in Wood-Ljungdahl (WL) pathway and 3-hydroxypropionate (3-HP) bicycle were absent in all MAGs and in the entire metagenome dataset, suggesting that both pathways may not be important for carbon fixation at both locations. The marker gene encoding ATP citrate lyase (*aclAB*), an enzyme involved in reductive tricarboxylic acid (rTCA) cycle, was also absent in all MAGs. ATP citrate lyase catalyzes citrate cleavage in rTCA cycle but in *Aquificaceae*, this reaction is catalyzed by the combined action of citryl-CoA synthetase (*ccsAB*) and citryl-CoA lyase (*ccl*) (Aoshima et al., 2004a,b) which were found in our *Aquificota* MAG (*UBA11096*) from Pisciarelli metagenome indicating potential for rTCA.

Potential for methanogenesis was absent in MAGs from both locations. Although the gene encoding hydrogen disulfide reductase (*hdrABC*) involved in methanogenesis was found in *Firmicutes* (*Sulfobacillus*, *R501*, and unknown species of the *Sulfobacillaceae* family), *Gammaproteobacteria* (*Acidithiobacillus*), *Aquificota* (*UBA11096*), and *Thermoproteota* (*Metallosphaera*) MAGs, the gene encoding key enzyme, methyl-CoM reductase (*mcr*) in methanogenesis was absent. Given the absence of *mcr* gene, the absence of genes encoding other enzymes involved in methanogenesis especially in the

*Metallosphaera* MAG that was 100% complete, and the absence of  $\delta^{13}\text{C}$  values lower than  $-30\text{‰}$ , it is likely that the *hdrABC* genes in these MAGs are not used in methanogenesis but are most likely used in sulfur metabolism (Mander et al., 2004; Wang et al., 2019). Potential for methane oxidation (methanol dehydrogenase; *mdh1* and particulate methane monooxygenase; *pmo*) was also absent in all MAGs.

### Sulfur metabolism

Sulfur isotope values ( $\delta^{34}\text{S}$ ) measured in deposits from both locations (Figure 9D) are characteristic of sulfur with sedimentary origin, but  $\delta^{34}\text{S}$  values ( $-0.83$  to  $2.62\text{‰}$ ) measured in water and mud where oxidation of  $\text{H}_2\text{S}$  is extensive, fall within the range for  $\text{SO}_4^{2-}$  formed from sulfide oxidation ( $-2.5$  to  $2.4\text{‰}$ ; Allard et al., 1991). In acidic environments like Solfatara and Pisciarelli, abiotic oxidation of  $\text{H}_2\text{S}$ -rich gas produced from the disproportionation of volcanic  $\text{SO}_2$  is inhibited (D'Imperio et al., 2008), thus providing a great habitat for sulfur-oxidizing microorganisms that utilize  $\text{H}_2\text{S}$  for energy generation. The abundance in  $\text{H}_2\text{S}$  is consistent with the presence of genes encoding enzymes involved in the oxidation of a variety of reduced sulfur compounds ( $\text{H}_2\text{S}$ ,  $\text{S}^0$  or  $\text{S}_2\text{O}_3^{2-}$ ) at both locations. Genes encoding the enzyme, sulfide:quinone oxidoreductases (*sqr*) for  $\text{H}_2\text{S}$  oxidation to elemental sulfur ( $\text{S}^0$ ) were detected in all MAGs except one *Thermoproteota* MAG (*Desulfurococcus*; Figures 8B,C). The presence of *sqr* gene in most MAGs is indicative of the importance of  $\text{H}_2\text{S}$  oxidation to microbial communities at both locations.  $\text{S}^0$  formed can be reduced



to H<sub>2</sub>S by the enzyme molybdopterine sulfur reductase (*sreABC*) or disproportionated to H<sub>2</sub>S, thiosulfate (S<sub>2</sub>O<sub>3</sub><sup>2-</sup>) and sulfite (SO<sub>3</sub><sup>2-</sup>) by sulfur oxygenase reductase (*SOR*). The *sreABC* gene was found in *Thermoproteota* MAG (*Acidianus*) while *SOR* gene was found in *Firmicutes* (*Sulfobacillus*, *R501*, and *Acidibacillus*) *Gammaproteobacteria* (*Acidithiobacillus*) and *Thermoproteota* (*Acidianus* and *Sulfuracidifex*) MAGs.

Thiosulfate (S<sub>2</sub>O<sub>3</sub><sup>2-</sup>) may not be available for microbial metabolism since it disproportionates to S<sup>0</sup> and SO<sub>3</sub><sup>2-</sup> at pH < 4 (Nordstrom et al., 2004); however, microbial communities exhibited potential to utilize S<sub>2</sub>O<sub>3</sub><sup>2-</sup>. Thiosulfate can be oxidized to SO<sub>4</sub><sup>2-</sup> via the *Sox* system (*soxXYZABCD*) which we detected in *Gammaproteobacteria* (*Acidithiobacillus*) and *Aquificota* (*UBA11096*) MAGs. In both MAGs, *soxCD* was absent suggesting that they oxidize S<sub>2</sub>O<sub>3</sub><sup>2-</sup> to S<sup>0</sup> instead of SO<sub>4</sub><sup>2-</sup> which is consistent with studies that identified the *sox* cluster without *soxCD* in *Acidithiobacillus* (Wang et al., 2019). Thiosulfate can also be oxidized to tetrathionate (S<sub>4</sub>O<sub>6</sub><sup>2-</sup>) by thiosulfate:quinol oxidoreductase (*doxDA*) or reduced to SO<sub>3</sub><sup>2-</sup> by thiosulfate:cyanide sulfur transferase (*tst*). The *doxDA* gene was found in all *Sulfolobaceae* MAGs (*Acidianus*, *Metallosphaera*, *Sulfuracidifex*) and in the *Firmicutes* (*R501*) MAG, while *tst* gene was found in 2 *Thermoproteota* (*Pyrobaculum*, *Metallosphaera*) MAGs and most *Firmicutes* MAGs. H<sub>2</sub>S can be regenerated by reducing SO<sub>4</sub><sup>2-</sup> via dissimilatory sulfate reduction (DSR). Genes encoding enzymes (dissimilatory sulfite reductase; *dsrAB*, adenylylsulfate reductase; *aprAB*, and sulfate adenylyltransferase; *sat*) involved in DSR were detected in one *Thermoproteota* (*Pyrobaculum*) MAG. The presence of both genes encoding enzymes involved in sulfur oxidation and reduction in some MAGs implies that microbial communities in Solfatara–Pisciarelli systems may take advantage of the high energy yield that results from coupling sulfur oxidation to sulfur reduction, which has been previously observed in other microbial community studies (Glamoclija et al., 2004; Crognale et al., 2022). Our results are consistent with studies that found the abundance of organisms capable of utilizing sulfur (Inskeep et al., 2013) and an enrichment of genes (*sqr*, *doxDA*, and *SOR*) involved in metabolizing reduced sulfur compounds in acidic hot springs (Colman et al., 2019a).

## Nitrogen metabolism

Our results showed that nitrogen metabolism may not be an important energy-yielding pathway for microbial communities even in Pisciarelli mud pools where NH<sub>4</sub><sup>+</sup> was abundant (Figures 8B,D). Exceptionally low δ<sup>15</sup>N values were observed at both locations (Figure 9B) and the lowest δ<sup>15</sup>N values ever measured were found in the Pisciarelli epilithic microbial layer. These extremely low δ<sup>15</sup>N values are difficult to explain in the context of metabolic potential present in our MAGs or metagenome fragments. Low and negative δ<sup>15</sup>N values are sometimes linked to microbial ammonia oxidation and/or nitrogen fixation (Tozer et al., 2005; Havig et al., 2011). Although Crognale et al. (2022) reported ammonia oxidation to be the most likely metabolic pathway in Pisciarelli mud pools due to its high energy yield, the absence of genes encoding enzymes involved in ammonia oxidation (ammonia monooxygenase; *amoCAB* and hydroxylamine dehydrogenase; *hao*) or nitrogen fixation (*nifD*, *nifK*, and *nifH*) in our MAGs and metagenome dataset indicates that microbial nitrogen metabolism cannot explain the geochemistry we observed. Previously observed negative δ<sup>15</sup>N

values (about −10‰) have been associated with the dissolution of magmatic nitrogen in water at elevated temperatures and pressures (Labidi et al., 2020). While it is very likely, the mechanism by which magmatic nitrogen, high temperature and pressure would contribute to the extremely low δ<sup>15</sup>N values measured at Solfatara and Pisciarelli is unclear.

Evidence of denitrification which has not been linked to low and negative δ<sup>15</sup>N values was found in five MAGs (*Sulfobacillus*, *R501*, unknown species of the *Alicyclobacillaceae* family, *Pyrobaculum*, and *UBA11096*). However, none of the MAGs carried all the genes encoding enzymes for the complete denitrification pathway (nitrate reductase, *narGH* or *napA*; nitrite reductase, *nirK*; nitric oxide reductase, *norB*; nitrous oxide reductase, *nosZ*). The complete set of genes for denitrification were also absent in metagenome fragments. One Pisciarelli MAG (*UBA11096*) belonging to the family *Aquificaceae*, carried most of the denitrification genes except *nosZ* which is consistent with studies that found nitrous oxide (N<sub>2</sub>O) to be the end-product of denitrification in members of *Aquificaceae* (Nakagawa et al., 2004). Dissimilatory nitrate reduction to ammonia via nitrite reductases (*nirBD*) was detected only in the *Aquificaceae* MAG from Pisciarelli.

## Conclusion

Results from this study showed that Solfatara and Pisciarelli are lithologically similar but geochemically distinct. At Pisciarelli, we observed varying geochemistry among mud pools and fumarolic deposits, which results from subsurface fluid–rock interactions, whereas Solfatara substrates were geochemically similar. Shannon diversity was significantly different between locations but showed no significant difference across substrates. We found pH to be the most important driver of alpha diversity and microbial community composition. NMDS plot and ANOSIM showed that Solfatara’s microbial community structure exhibited no significant difference across substrates which also coincides with observed trends in geochemistry. In contrast, at Pisciarelli, microbial community structure followed trends in fluid availability rather than geochemical trends. Geochemically, water and mud from Pisciarelli large mud pool and water from Pisciarelli small mud pool clustered distinctly from fumarolic deposits, discharge channel mud and mud from Pisciarelli small pool. However, based on microbial communities, all water and mud samples clustered distinctly from fumarolic deposits that were the driest substrates analyzed; results showed that Pisciarelli fumarolic deposits were more similar to Solfatara samples than samples from Pisciarelli mud pools. Overall, the genus *Acidianus* dominated Pisciarelli water and *Pyrobaculum* was more abundant in Pisciarelli mud. Interestingly, Pisciarelli fumarolic deposits, epilithic microbial layer, and mud from small mud pool had a high number of viral sequences. Solfatara and Pisciarelli had distinct microbial communities; on average, *Acidianus* and *Pyrobaculum* dominated Pisciarelli while *Sulfobacillus* and *Acidibacillus* were dominant at Solfatara. Although microbial communities were distinct between the two locations and between Pisciarelli substrates, MAGs indicated functional redundancy. For example, the potential to reduce H<sub>2</sub>S to S<sup>0</sup> was observed in almost all MAGs. Further, MAGs showed that microbial communities inhabiting both locations took advantage of the major volcanic gases (CO<sub>2</sub> and H<sub>2</sub>S) via carbon fixation and sulfur oxidation. The 3HP/4-HB pathway found in most archaeal MAGs is most likely the primary mode of carbon fixation in Pisciarelli mud pools dominated by

(hyper)thermophilic archaea whereas CBB cycle is most likely the primary carbon fixation pathway in all other environments where bacteria was abundant. At both locations, sulfur cycling is represented by oxidation of H<sub>2</sub>S-rich volcanic gas and other reduced sulfur compounds. Comparative geochemical and metagenomic analyses demonstrate that ecological differences across substrates are not a widespread phenomenon but specific to the system. Therefore, this study demonstrates the importance of analyzing different substrates of CHSS to understand the full range of microbial ecology to avoid biased ecological assessment.

## Data availability statement

The datasets presented in this study can be found in online repositories. The names of the repository/repositories and accession number(s) can be found below: <https://www.ncbi.nlm.nih.gov/Bioproject> accession PRJNA889931.

## Author contributions

MG, AS, MF, GN, and CT designed and organized the project. MG, RS, MP, AM collected the samples. IU, RB, MF, and MG collected the data. IU, MG, and MF contributed to the data processing and analyses. IU and MG wrote the manuscript. All authors contributed to the article and approved the submitted version.

## Funding

This research was enabled through the Alfred P. Sloan Foundation's support of the Deep Carbon Observatory Deep Earth Carbon Degassing program (DECADE) to MG and Rutgers Faculty Program Start Up. IU was supported by Rutgers University Transform Graduate Fellowship.

## Acknowledgments

We would like to thank Ying Lin at UCR for re-running samples to confirm δ<sup>15</sup>N values and Ashley E. Murphy for running samples on XRF. We thank the Office of Advanced Research Computing (OARC) at Rutgers, The State University of New Jersey for providing access to the Amarel cluster and the associated resources that have

## References

- Aiuppa, A., Tamburello, G., Di Napoli, R., Cardellini, C., Chiodini, G., Giudice, G., et al. (2013). First observations of the fumarolic gas output from a restless caldera: implications for the current period of unrest (2005–2013) at Campi Flegrei. *Geochem. Geophys.* 14, 4153–4169. doi: 10.1002/ggge.20261
- Allard, P., Maiorani, A., Tedesco, D., Cortecchi, G., and Turi, B. (1991). Isotopic study of the origin of sulfur and carbon in Solfatara fumaroles, Campi Flegrei caldera. *J. Volcanol. Geotherm. Res.* 48, 139–159. doi: 10.1016/0377-0273(91)90039-3
- Alneberg, J., Bjarnason, B. S., De Bruijn, I., Schirmer, M., Quick, J., Ijaz, U. Z., et al. (2014). Binning metagenomic contigs by coverage and composition. *Nat. Methods* 11, 1144–1146. doi: 10.1038/nmeth.3103
- Alsop, E. B., Boyd, E. S., and Raymond, J. (2014). Merging metagenomics and geochemistry reveals environmental controls on biological diversity and evolution. *BMC Ecol.* 14:16. doi: 10.1186/1472-6785-14-16
- Amenabar, M. J., and Boyd, E. S. (2019). A review of the mechanisms of mineral-based metabolism in early earth analog rock-hosted hydrothermal ecosystems. *World J. Microbiol. Biotechnol.* 35:29. doi: 10.1007/s11274-019-2604-2
- Amenabar, M. J., Shock, E. L., Roden, E. E., Peters, J. W., and Boyd, E. S. (2017). Microbial substrate preference dictated by energy demand rather than supply. *Nat. Geosci.* 10, 577–581. doi: 10.1038/ngeo2978
- Aoshima, M., Ishii, M., and Igarashi, Y. (2004a). A novel enzyme, citryl-CoA lyase, catalysing the second step of the citrate cleavage reaction in *Hydrogenobacter thermophilus* TK-6. *Mol. Microbiol.* 52, 763–770. doi: 10.1111/j.1365-2958.2004.04010.x
- Aoshima, M., Ishii, M., and Igarashi, Y. (2004b). A novel enzyme, citryl-CoA synthetase, catalysing the first step of the citrate cleavage reaction in *Hydrogenobacter thermophilus* TK-6. *Mol. Microbiol.* 52, 751–761. doi: 10.1111/j.1365-2958.2004.04009.x

contributed to the results reported in this manuscript. We thank two reviewers for their thoughtful and constructive comments which have significantly improved this manuscript.

## Conflict of interest

The authors declare that the research was conducted in the absence of any commercial or financial relationships that could be construed as a potential conflict of interest.

## Publisher's note

All claims expressed in this article are solely those of the authors and do not necessarily represent those of their affiliated organizations, or those of the publisher, the editors and the reviewers. Any product that may be evaluated in this article, or claim that may be made by its manufacturer, is not guaranteed or endorsed by the publisher.

## Supplementary material

The Supplementary material for this article can be found online at: <https://www.frontiersin.org/articles/10.3389/fmicb.2023.1066406/full#supplementary-material>

### SUPPLEMENTARY FIGURE 1

Ballot based on Principal Component Analysis (PCA) using bulk elemental composition of mud and fumarolic deposits.

### SUPPLEMENTARY FIGURE 2

Taxonomic profile of Solfatara and Pisciarelli microorganisms based on metagenomic profiling. Sequences not classified at the domain level and species with relative abundance less than 0.01% were grouped into unclassified and low abundance species. All kitome were grouped into contaminant. Samples collected from Pisciarelli large pool are denoted by PLP, Pisciarelli small pool by PSP, Pisciarelli fumarole by PF, Solfatara mud pool by SMP, and Solfatara fumarole by SF. W represents water, M for mud, MO for mud outlet, E for epilithic microbial layer from dry mud wall, and D for deposits samples. Samples labeled a and b are replicates sampled from the same spot. Sample SMP-M\_a1 and SMP-M\_a1.2 are sequencing replicates.

### SUPPLEMENTARY FIGURE 3

Relative abundance of kitome families. Kitome families with average abundance of <1% were grouped into Others <1%.

### SUPPLEMENTARY FIGURE 4

Estimation of the coverage of microbial communities in (A) Solfatara and (B) Pisciarelli. The empty circles on the curves represent community coverage estimate at the sequencing effort applied. The top and bottom horizontal red dashed indicate 100 and 95% average community coverage, respectively. The arrows are the Nonpareil diversity estimates.

- Arif, S., Willenberg, C., Dreyer, A., Nacke, H., and Hoppert, M. (2021). Sasso Pisano geothermal field environment Harbours diverse Ktedonobacteria representatives and illustrates habitat-specific adaptations. *Microorganisms* 9:1402. doi: 10.3390/microorganisms9071402
- Aulitto, M., Gallo, G., Puopolo, R., Mormone, A., Limauro, D., Contursi, P., et al. (2021). Genomic insight of *Alicyclobacillus* Mali FL18 isolated from an arsenic-rich hot spring. *Front. Microbiol.* 12:669. doi: 10.3389/fmicb.2021.639697
- Bankevich, A., Nurk, S., Antipov, D., Gurevich, A. A., Dvorkin, M., Kulikov, A. S., et al. (2012). SPAdes: a new genome assembly algorithm and its applications to single-cell sequencing. *J. Comput. Biol.* 19, 455–477. doi: 10.1089/cmb.2012.0021
- Benson, C. A., Bizzoco, R. W., Lipson, D. A., and Kelley, S. T. (2011). Microbial diversity in nonsulfur, sulfur and iron geothermal steam vents. *FEMS Microbiol. Ecol.* 76, 74–88. doi: 10.1111/j.1574-6941.2011.01047.x
- Berg, I. A., Kockelkorn, D., Ramos-Vera, W. H., Say, R. F., Zarzycki, J., Hügler, M., et al. (2010). Autotrophic carbon fixation in archaea. *Nat. Rev. Microbiol.* 8, 447–460. doi: 10.1038/nrmicro2365
- Bolger, A. M., Lohse, M., and Usadel, B. (2014). Trimmomatic: a flexible trimmer for Illumina sequence data. *Bioinformatics* 30, 2114–2120. doi: 10.1093/bioinformatics/btu170
- Boyd, E. S., Hamilton, T. L., Spear, J. R., Lavin, M., and Peters, J. W. (2010). [FeFe]-hydrogenase in Yellowstone National Park: evidence for dispersal limitation and phylogenetic niche conservatism. *ISME J.* 4, 1485–1495. doi: 10.1038/ismej.2010.76
- Boyer, G. M., Schubotz, F., Summons, R. E., Woods, J., and Shock, E. L. (2020). Carbon oxidation state in microbial polar lipids suggests adaptation to hot spring temperature and redox gradients. *Front. Microbiol.* 11:229. doi: 10.3389/fmicb.2020.00229
- Brock, T. D. (1985). Life at high temperatures. *Science* 230, 132–138. doi: 10.1126/science.230.4722.132
- Brumfield, K. D., Huq, A., Colwell, R. R., Olds, J. L., and Leddy, M. B. (2020). Microbial resolution of whole genome shotgun and 16S amplicon metagenomic sequencing using publicly available NEON data. *PLoS One* 15:e0228899. doi: 10.1371/journal.pone.0228899
- Caldwell, P. E., MacLean, M. R., and Norris, P. R. (2007). Ribulose biphosphate carboxylase activity and a Calvin cycle gene cluster in *Sulfobacillus* species. *Microbiology* 153, 2231–2240. doi: 10.1099/mic.0.2007/006262-0
- Caliro, S., Chiodini, G., Moretti, R., Avino, R., Granieri, D., Russo, M., et al. (2007). The origin of the fumaroles of La Solfatara (Campi Flegrei, South Italy). *Geochim. Cosmochim. Acta* 71, 3040–3055. doi: 10.1016/j.gca.2007.04.007
- Cerqueira, T., Barroso, C., Froufe, H., Egas, C., and Bettencourt, R. (2018). Metagenomic signatures of microbial communities in deep-sea hydrothermal sediments of Azores vent fields. *Microb. Ecol.* 76, 387–403. doi: 10.1007/s00248-018-1144-x
- Chaumeil, P.-A., Mussig, A. J., Hugenholtz, P., and Parks, D. H. (2020). GTDB-Tk: a toolkit to classify genomes with the genome taxonomy database. *Bioinformatics* 36, 1925–1927. doi: 10.1093/bioinformatics/btz848
- Chiodini, G., Avino, R., Caliro, S., and Minopoli, C. (2011). Temperature and pressure gas geoidicators at the Solfatara fumaroles (Campi Flegrei). *Ann. Geophys.* 54:107245. doi: 10.4401/ag-5002
- Chiodini, G., Caliro, S., Avino, R., Bini, G., Giudicepietro, F., De Cesare, W., et al. (2021). Hydrothermal pressure-temperature control on CO<sub>2</sub> emissions and seismicity at Campi Flegrei (Italy). *J. Volcanol. Geotherm. Res.* 414:107245. doi: 10.1016/j.jvolgeores.2021.107245
- Chiodini, G., Caliro, S., Cardellini, C., Granieri, D., Avino, R., Baldini, A., et al. (2010). Long-term variations of the Campi Flegrei, Italy, volcanic system as revealed by the monitoring of hydrothermal activity. *J. Geophys. Res. Solid Earth* 115:B03205. doi: 10.1029/2008JB006258
- Chiodini, G., Frondini, F., Cardellini, C., Granieri, D., Marini, L., and Ventura, G. (2001). CO<sub>2</sub> degassing and energy release at Solfatara volcano, Campi Flegrei, Italy. *J. Geophys. Res. Solid Earth* 106, 16213–16221. doi: 10.1029/2001JB000246
- Ciniglia, C. V. (2005). Influences of geochemical and mineralogical constraints on algal distribution in acidic hydrothermal environments: Pisciarelli (Naples, Italy) as a model site. *Arch. Hydrobiol.* 162, 121–142. doi: 10.1127/0003-9136/2005/0162-0121
- Cole, J. K., Peacock, J. P., Dodsworth, J. A., Williams, A. J., Thompson, D. B., Dong, H., et al. (2013). Sediment microbial communities in great boiling spring are controlled by temperature and distinct from water communities. *ISME J.* 7, 718–729. doi: 10.1038/ismej.2012.157
- Colman, D. R., Feyhl-Buska, J., Robinson, K. J., Fecteau, K. M., Xu, H., Shock, E. L., et al. (2016). Ecological differentiation in planktonic and sediment-associated chemotrophic microbial populations in Yellowstone hot springs. *FEMS Microbiol. Ecol.* 92:137. doi: 10.1093/femsec/fiw137
- Colman, D. R., Lindsay, M. R., Amenabar, M. J., and Boyd, E. S. (2019a). The intersection of geology, geochemistry, and microbiology in continental hydrothermal systems. *Astrobiology* 19, 1505–1522. doi: 10.1089/ast.2018.2016
- Colman, D. R., Lindsay, M. R., and Boyd, E. S. (2019b). Mixing of meteoric and geothermal fluids supports hyperdiverse chemosynthetic hydrothermal communities. *Nat. Commun.* 10:681. doi: 10.1038/s41467-019-08499-1
- Cox, A., Shock, E. L., and Havig, J. R. (2011). The transition to microbial photosynthesis in hot spring ecosystems. *Chem. Geol.* 280, 344–351. doi: 10.1016/j.chemgeo.2010.11.022
- Crognale, S., Venturi, S., Tassi, F., Rossetti, S., Cabassi, J., Capecchiacci, F., et al. (2022). Geochemical and microbiological profiles in hydrothermal extreme acidic environments (Pisciarelli Spring, Campi Flegrei, Italy). *FEMS Microbiol. Ecol.* 98:fiac088. doi: 10.1093/femsec/fiac088
- Crognale, S., Venturi, S., Tassi, F., Rossetti, S., Rashed, H., Cabassi, J., et al. (2018). Microbiome profiling in extremely acidic soils affected by hydrothermal fluids: the case of the Solfatara crater (Campi Flegrei, southern Italy). *FEMS Microbiol. Ecol.* 94:fiy190. doi: 10.1093/femsec/fiy190
- De Natale, G., Troise, C., Mark, D., Mormone, A., Piochi, M., Di Vito, M. A., et al. (2016). The Campi Flegrei deep drilling project (CFDDP): new insight on caldera structure, evolution and hazard implications for the Naples area (Southern Italy). *Geochem. Geophys.* 17, 4836–4847. doi: 10.1002/2015GC006183
- DeSantis, T. Z., Hugenholtz, P., Larsen, N., Rojas, M., Brodie, E. L., Keller, K., et al. (2006). Greengenes, a chimera-checked 16S rRNA gene database and workbench compatible with ARB. *Appl. Environ. Microbiol.* 72, 5069–5072. doi: 10.1128/AEM.03006-05
- D’Imperio, S., Lehr, C. R., Oduro, H., Druschel, G., Kühl, M., and McDermott, T. R. (2008). Relative importance of H<sub>2</sub> and H<sub>2</sub>S as energy sources for primary production in geothermal springs. *Appl. Environ. Microbiol.* 74, 5802–5808. doi: 10.1128/AEM.00852-08
- Ellis, D. G., Bizzoco, R. W., and Kelley, S. T. (2008). Halophilic archaea determined from geothermal steam vent aerosols. *Environ. Microbiol.* 10, 1582–1590. doi: 10.1111/j.1462-2920.2008.01574.x
- Fedele, A., Somma, R., Troise, C., Holmberg, K., De Natale, G., and Matano, F. (2021). Time-lapse landform monitoring in the Pisciarelli (Campi Flegrei-Italy) fumarole field using UAV photogrammetry. *Remote Sens.* 13:118. doi: 10.3390/rs13010118
- Fournier, R. O. (1989). Geochemistry and dynamics of the Yellowstone National Park hydrothermal system. *Annu. Rev. Earth Planet. Sci.* 17, 13–53. doi: 10.1146/annurev.ea.17.050189.000305
- Fullerton, K. M., Schrenk, M. O., Yücel, M., Manini, E., Basili, M., Rogers, T. J., et al. (2021). Effect of tectonic processes on biosphere–geosphere feedbacks across a convergent margin. *Nat. Geosci.* 14, 301–306. doi: 10.1038/s41561-021-00725-0
- Glamoclija, M., Garrel, L., Berthon, J., and López-García, P. (2004). Biosignatures and bacterial diversity in hydrothermal deposits of Solfatara Crater, Italy. *Geomicrobiol. J.* 21, 529–541. doi: 10.1080/01490450490888235
- Hamilton, T., Vogl, K., Bryant, D., Boyd, E., and Peters, J. (2012). Environmental constraints defining the distribution, composition, and evolution of chlorophototrophs in thermal fields of Yellowstone National Park. *Geobiology* 10, 236–249. doi: 10.1111/j.1472-4669.2011.00296.x
- Havig, J. R., Raymond, J., Meyer-Dombard, D. A. R., Zolotova, N., and Shock, E. L. (2011). Merging isotopes and community genomics in a siliceous sinter-depositing hot spring. *J. Geophys. Res.* 116:G01005. doi: 10.1029/2010JG001415
- Hou, W., Wang, S., Dong, H., Jiang, H., Briggs, B. R., Peacock, J. P., et al. (2013). A comprehensive census of microbial diversity in hot springs of Tengchong, Yunnan Province China using 16S rRNA gene pyrosequencing. *PLoS One* 8:e53350. doi: 10.1371/journal.pone.0053350
- Huber, R., Sacher, M., Vollmann, A., Huber, H., and Rose, D. (2000). Respiration of arsenate and selenate by hyperthermophilic archaea. *Syst. Appl. Microbiol.* 23, 305–314. doi: 10.1016/S0723-2020(00)80058-2
- Husson, O. (2013). Redox potential (eh) and pH as drivers of soil/plant/microorganism systems: a transdisciplinary overview pointing to integrative opportunities for agronomy. *Plant Soil* 362, 389–417. doi: 10.1007/s11104-012-1429-7
- Iacono, R., Cobucci-Ponzano, B., De Lise, F., Curci, N., Maurelli, L., Moracci, M., et al. (2020). Spatial metagenomics of three geothermal sites in Pisciarelli hot spring focusing on the biochemical resources of the microbial consortia. *Molecules* 25:4023. doi: 10.3390/molecules25174023
- Inskip, W. P., Jay, Z. J., Tringe, S. G., Herrgard, M., and Rusch, D. B. (2013). The YNP metagenome project: environmental parameters responsible for microbial distribution in the Yellowstone geothermal ecosystem. *Front. Microbiol.* 4:67. doi: 10.3389/fmicb.2013.00067
- Jain, C., Rodriguez-R, L. M., Phillippy, A. M., Konstantinidis, K. T., and Aluru, S. (2018). High throughput ANI analysis of 90K prokaryotic genomes reveals clear species boundaries. *Nat. Commun.* 9:5114. doi: 10.1038/s41467-018-07641-9
- Kanehisa, M., Sato, Y., and Morishima, K. (2016). BlastKOALA and GhostKOALA: KEGG tools for functional characterization of genome and metagenome sequences. *J. Mol. Biol.* 428, 726–731. doi: 10.1016/j.jmb.2015.11.006
- Kang, D. D., Li, F., Kirton, E., Thomas, A., Egan, R., An, H., et al. (2019). MetaBAT 2: an adaptive binning algorithm for robust and efficient genome reconstruction from metagenome assemblies. *PeerJ* 7:e7359. doi: 10.7717/peerj.7359
- Karstens, L., Asquith, M., Davin, S., Fair, D., Gregory, W. T., Wolfe, A. J., et al. (2019). Controlling for contaminants in low-biomass 16S rRNA gene sequencing experiments. *mSystems* 4:e00290-19. doi: 10.1128/mSystems.00290-19
- Kimbrough, D. E., Kouame, Y., Moheban, P., and Springthorpe, S. (2006). The effect of electrolysis and oxidation–reduction potential on microbial survival, growth, and disinfection. *Int. J. Environ. Pollut.* 27, 211–221. doi: 10.1504/IJEP.2006.010464
- Kono, T., Mehrotra, S., Endo, C., Kizu, N., Matusda, M., Kimura, H., et al. (2017). A RuBisCO-mediated carbon metabolic pathway in methanogenic archaea. *Nat. Commun.* 8:14007. doi: 10.1038/ncomms14007
- Labidi, J., Barry, P. H., Bekaert, D. V., Broadley, M. W., Marty, B., Giunta, T., et al. (2020). Hydrothermal 15 N 15 N abundances constrain the origins of mantle nitrogen. *Nature* 580, 367–371. doi: 10.1038/s41586-020-2173-4



- Lezcano, M. Á., Moreno-Paz, M., Carrizo, D., Prieto-Ballesteros, O., Fernández-Martínez, M. Á., Sánchez-García, L., et al. (2019). Biomarker profiling of microbial mats in the geothermal band of Cerro Caliente, Deception Island (Antarctica): life at the edge of heat and cold. *Astrobiology* 19, 1490–1504. doi: 10.1089/ast.2018.2004
- Li, D., Liu, C.-M., Luo, R., Sadakane, K., and Lam, T.-W. (2015). MEGAHT: an ultra-fast single-node solution for large and complex metagenomics assembly via succinct de Bruijn graph. *Bioinformatics* 31, 1674–1676. doi: 10.1093/bioinformatics/btv033
- Lindsay, M. R., Amenabar, M. J., Fecteau, K. M., Debes, R. V., Fernandes Martins, M. C., Fristad, K. E., et al. (2018). Subsurface processes influence oxidant availability and chemoautotrophic hydrogen metabolism in Yellowstone hot springs. *Geobiology* 16, 674–692. doi: 10.1111/gbi.12308
- Lindsay, M. R., Colman, D. R., Amenabar, M. J., Fristad, K. E., Fecteau, K. M., Debes, R. V., et al. (2019). Probing the geological source and biological fate of hydrogen in Yellowstone hot springs. *Environ. Microbiol.* 21, 3816–3830. doi: 10.1111/1462-2920.14730
- Lowenstern, J. B., Bergfeld, D., Evans, W. C., and Hunt, A. G. (2015). Origins of geothermal gases at Yellowstone. *J. Volcanol. Geotherm. Res.* 302, 87–101. doi: 10.1016/j.jvolgeores.2015.06.010
- Mander, G. J., Pierik, A. J., Huber, H., and Hedderich, R. (2004). Two distinct heterodisulfide reductase-like enzymes in the sulfate-reducing archaeon *Archaeoglobus profundus*. *Eur. J. Biochem.* 271, 1106–1116. doi: 10.1111/j.1432-1033.2004.04013.x
- Mardanov, A. V., Gumerov, V. M., Beletsky, A. V., and Ravin, N. V. (2018). Microbial diversity in acidic thermal pools in the Uzon caldera, Kamchatka. *Antonie Van Leeuwenhoek* 111, 35–43. doi: 10.1007/s10482-017-0924-5
- Marlow, J. J., Colocci, I., Jungbluth, S. P., Weber, N. M., Gartman, A., and Kallmeyer, J. (2020). Mapping metabolic activity at single cell resolution in intact volcanic fumarole sediment. *FEMS Microbiol. Lett.* 367:fnaa031. doi: 10.1093/femsle/fnaa031
- Martini, M., Giannini, L., Buccianti, A., Prati, F., Legittimo, P. C., Iozzelli, P., et al. (1991). 1980–1990: ten years of geochemical investigation at Phlegrean fields (Italy). *J. Volcanol. Geotherm. Res.* 48, 161–171. doi: 10.1016/0377-0273(91)90040-7
- Medrano-Santillana, M., Souza-Brito, E. M., Duran, R., Gutierrez-Corona, F., and Reyna-López, G. E. (2017). Bacterial diversity in fumarole environments of the Parícutin volcano, Michoacán (Mexico). *Extremophiles* 21, 499–511. doi: 10.1007/s00792-017-0920-8
- Menzel, P., Gudbergdóttir, S. R., Rike, A. G., Lin, L., Zhang, Q., Contursi, P., et al. (2015). Comparative metagenomics of eight geographically remote terrestrial hot springs. *Microb. Ecol.* 70, 411–424. doi: 10.1007/s00248-015-0576-9
- Menzel, P., Ng, K. L., and Krogh, A. (2016). Fast and sensitive taxonomic classification for metagenomics with *kaiju*. *Nat. Commun.* 7:11257. doi: 10.1038/ncomms11257
- Meyer, F., Paarmann, D., D'Souza, M., Olson, R., Glass, E. M., Kubal, M., et al. (2008). The metagenomics RAST server—a public resource for the automatic phylogenetic and functional analysis of metagenomes. *BMC Bioinformatics* 9:386. doi: 10.1186/1471-2105-9-386
- Miller, S. R., Strong, A. L., Jones, K. L., and Ungerer, M. C. (2009). Bar-coded pyrosequencing reveals shared bacterial community properties along the temperature gradients of two alkaline hot springs in Yellowstone National Park. *Appl. Environ. Microbiol.* 75, 4565–4572. doi: 10.1128/AEM.02792-08
- Moreras-Martí, A., Fox-Powell, M., Zerkle, A. L., Stueeken, E., Gazquez, F., Brand, H. E., et al. (2021). Volcanic controls on the microbial habitability of Mars-analogue hydrothermal environments. *Geobiology* 19, 489–509. doi: 10.1111/gbi.12459
- Moretti, R., De Natale, G., and Troise, C. (2020). *Hydrothermal Versus Magmatic: Geological Views and Clues Into the Unrest Dilemma at Campi Flegrei/Vesuvius, Campi Flegrei, and Campanian Volcanism*. Amsterdam, Netherlands: Elsevier, 371–406.
- Munson-McGee, J. H., Peng, S., Dewerff, S., Stepanauskas, R., Whitaker, R. J., Weitz, J. S., et al. (2018). A virus or more in (nearly) every cell: ubiquitous networks of virus–host interactions in extreme environments. *ISME J.* 12, 1706–1714. doi: 10.1038/s41396-018-0071-7
- Nakagawa, S., Nakamura, S., Inagaki, F., Takai, K., Shirai, N., and Sako, Y. (2004). *Hydrogenivirga caldilitoris* gen. nov., sp. nov., a novel extremely thermophilic, hydrogen- and sulfur-oxidizing bacterium from a coastal hydrothermal field. *Int. J. Syst. Evol. Microbiol.* 54, 2079–2084. doi: 10.1099/ijs.0.03031-0
- Nordstrom, D., Ball, J., and McCleskey, R. (2004). “Oxidation reactions for reduced Fe, As, and S in thermal outflows of” in *Water-Rock Interaction*. eds. R. Wanty and R. Seal (London, UK: Taylor and Francis Group), 59–62.
- Nordstrom, D. K., Ball, J. W., and McCleskey, R. B. (2005). “Ground water to surface water: geochemistry of thermal outflows in Yellowstone National Park” in *Geothermal Biology and Geochemistry in Yellowstone National Park*. eds. W. Inskeep and T. R. McDermott (Bozeman, MT: Montana State University), 73–94.
- Nordstrom, D. K., McCleskey, R. B., and Ball, J. W. (2009). Sulfur geochemistry of hydrothermal waters in Yellowstone National Park: IV acid–sulfate waters. *Appl. Geochem.* 24, 191–207. doi: 10.1016/j.apgeochem.2008.11.019
- Oliverio, A. M., Power, J. F., Washburne, A., Cary, S. C., Stott, M. B., and Fierer, N. (2018). The ecology and diversity of microbial eukaryotes in geothermal springs. *ISME J.* 12, 1918–1928. doi: 10.1038/s41396-018-0104-2
- Parks, D. H., Imelfort, M., Skennerton, C. T., Hugenholtz, P., and Tyson, G. W. (2015). CheckM: assessing the quality of microbial genomes recovered from isolates, single cells, and metagenomes. *Genome Res.* 25, 1043–1055. doi: 10.1101/gr.186072.114
- Piochi, M., Kilburn, C., Di Vito, M., Mormone, A., Tramelli, A., Troise, C., et al. (2014). The volcanic and geothermally active Campi Flegrei caldera: an integrated multidisciplinary image of its buried structure. *Int. J. Earth Sci.* 103, 401–421. doi: 10.1007/s00531-013-0972-7
- Piochi, M., Mormone, A., Balassone, G., Strauss, H., Troise, C., and De Natale, G. (2015). Native sulfur, sulfates and sulfides from the active Campi Flegrei volcano (southern Italy): genetic environments and degassing dynamics revealed by mineralogy and isotope geochemistry. *J. Volcanol. Geotherm. Res.* 304, 180–193. doi: 10.1016/j.jvolgeores.2015.08.017
- Podar, P. T., Yang, Z., Björnsdóttir, S. H., and Podar, M. (2020). Comparative analysis of microbial diversity across temperature gradients in hot springs from Yellowstone and Iceland. *Front. Microbiol.* 11:1625. doi: 10.3389/fmicb.2020.01625
- Poichi, M. M. A., Strauss, H., and Balassone, G. (2019). The acid sulfate zone and the mineral alteration styles of the Roman Puteoli (Neapolitan area, Italy): clues on fluid fracturing progression at the Campi Flegrei volcano. *Solid Earth* 10, 1809–1831. doi: 10.5194/se-10-1809-2019
- Power, J. F., Carere, C. R., Lee, C. K., Wakerley, G. L., Evans, D. W., Button, M., et al. (2018). Microbial biogeography of 925 geothermal springs in New Zealand. *Nat. Commun.* 9:2876. doi: 10.1038/s41467-018-05020-y
- Puopolo, R., Gallo, G., Mormone, A., Limauro, D., Contursi, P., Piochi, M., et al. (2020). Identification of a new heavy-metal-resistant strain of *Geobacillus stearothermophilus* isolated from a hydrothermally active volcanic area in southern Italy. *Int. J. Environ. Res. Public Health* 17:2678. doi: 10.3390/ijerph17082678
- R Core Team (2020). R: A language and environment for statistical computing. R Foundation for Statistical Computing. Vienna, Austria. Available at: <https://www.R-project.org/>
- Ranjan, R., Rani, A., Metwally, A., McGee, H. S., and Perkins, D. L. (2016). Analysis of the microbiome: advantages of whole genome shotgun versus 16S amplicon sequencing. *Biochem. Biophys. Res. Commun.* 469, 967–977. doi: 10.1016/j.bbrc.2015.12.083
- Rodriguez-R, L. M., Gunturu, S., Tiedje, J. M., Cole, J. R., and Constantinidis, K. T. (2018). Nonpareil 3: fast estimation of metagenomic coverage and sequence diversity. *mSystems* 3:e00039-18. doi: 10.1128/mSystems.00039-18
- Rolandi, G., De Natale, G., Kilburn, C. R., Troise, C., Somma, R., Di Lascio, M., et al. (2020a). *The 39 ka Campanian Ignimbrite Eruption: New Data on Source Area in the Campanian Plain Vesuvius, Campi Flegrei, and Campanian Volcanism*. Amsterdam, Netherlands: Elsevier, 175–205.
- Rolandi, G., Di Lascio, M., and Rolandi, R. (2020b). *The Neapolitan Yellow Tuff Eruption as the Source of the Campi Flegrei Caldera Vesuvius, Campi Flegrei, and Campanian Volcanism*. Amsterdam, Netherlands: Elsevier, 273–296.
- Scherf, U., and Buckel, W. (1993). Purification and properties of an iron-sulfur and FAD-containing 4-hydroxybutyryl-CoA dehydratase/vinylacetyl-CoA delta 3-delta 2-isomerase from *Clostridium aminobutyricum*. *Eur. J. Biochem.* 215, 421–429. doi: 10.1111/j.1432-1033.1993.tb18049.x
- Scherf, U., Söhling, B., Gottschalk, G., Linder, D., and Buckel, W. (1994). Succinate-ethanol fermentation in *Clostridium kluyveri*: purification and characterisation of 4-hydroxybutyryl-CoA dehydratase/vinylacetyl-CoA Δ3-Δ2-isomerase. *Arch. Microbiol.* 161, 239–245. doi: 10.1007/BF00248699
- Seemann, T. (2014). Prokka: rapid prokaryotic genome annotation. *Bioinformatics* 30, 2068–2069. doi: 10.1093/bioinformatics/btu153
- Seo, D. C., and DeLaune, R. D. (2010). Effect of redox conditions on bacterial and fungal biomass and carbon dioxide production in Louisiana coastal swamp forest sediment. *Sci. Total Environ.* 408, 3623–3631. doi: 10.1016/j.scitotenv.2010.04.043
- Sharp, Z. (2007). *Principles of Stable Isotope Geochemistry*. Pearson Education Inc., Upper Saddle River, NJ
- Sharp, C. E., Brady, A. L., Sharp, G. H., Grasby, S. E., Stott, M. B., and Dunfield, P. F. (2014). Humboldt's spa: microbial diversity is controlled by temperature in geothermal environments. *ISME J.* 8, 1166–1174. doi: 10.1038/ismej.2013.237
- Sheik, C. S., Reese, B. K., Twing, K. I., Sylvan, J. B., Grim, S. L., Schrenk, M. O., et al. (2018). Identification and removal of contaminant sequences from ribosomal gene databases: lessons from the census of deep life. *Front. Microbiol.* 9:840. doi: 10.3389/fmicb.2018.00840
- Shock, E. L., Holland, M., Amend, J. P., Osburn, G., and Fischer, T. P. (2010). Quantifying inorganic sources of geochemical energy in hydrothermal ecosystems, Yellowstone National Park, USA. *Geochim. Cosmochim. Acta* 74, 4005–4043. doi: 10.1016/j.gca.2009.08.036
- Solorzano, L. (1969). Determination of ammonia in natural waters by the phenol hypochlorite method. *Limnol. Oceanogr.* 14, 799–801.
- Strazzulli, A., Cobucci-Ponzano, B., Iacono, R., Giglio, R., Maurelli, L., Curci, N., et al. (2020). Discovery of hyperstable carbohydrate-active enzymes through metagenomics of extreme environments. *FEBS J.* 287, 1116–1137. doi: 10.1111/febs.15080
- Tozer, W. C., Hackell, D., Miers, D., and Silvester, W. (2005). Extreme isotopic depletion of nitrogen in New Zealand lithophytes and epiphytes; the result of diffusive uptake of atmospheric ammonia? *Oecologia* 144, 628–635. doi: 10.1007/s00442-005-0098-0
- Troiano, A., Di Giuseppe, M. G., Patella, D., Troise, C., and De Natale, G. (2014). Electromagnetic outline of the Solfatara–Pisciarelli hydrothermal system, Campi Flegrei (southern Italy). *J. Volcanol. Geotherm. Res.* 277, 9–21. doi: 10.1016/j.jvolgeores.2014.03.005
- Troise, C., De Natale, G., Schiavone, R., Somma, R., and Moretti, R. (2019). The Campi Flegrei caldera unrest: discriminating magma intrusions from hydrothermal effects and implications for possible evolution. *Earth-Sci. Rev.* 188, 108–122. doi: 10.1016/j.earscirev.2018.11.007

- Uritskiy, G. V., DiRuggiero, J., and Taylor, J. (2018). MetaWRAP—a flexible pipeline for genome-resolved metagenomic data analysis. *Microbiome* 6:158. doi: 10.1186/s40168-018-0541-1
- Valentino, G., and Stanzione, D. (2003). Source processes of the thermal waters from the Phlegraean fields (Naples, Italy) by means of the study of selected minor and trace elements distribution. *Chem. Geol.* 194, 245–274. doi: 10.1016/S0009-2541(02)00196-1
- Wall, K., Cornell, J., Bizzoco, R. W., and Kelley, S. T. (2015). Biodiversity hot spot on a hot spot: novel extremophile diversity in Hawaiian fumaroles. *MicrobiologyOpen* 4, 267–281. doi: 10.1002/mbo3.236
- Wang, S., Dong, H., Hou, W., Jiang, H., Huang, Q., Briggs, B. R., et al. (2014). Greater temporal changes of sediment microbial community than its waterborne counterpart in Tengchong hot springs, Yunnan Province, China. *Sci. Rep.* 4:7479. doi: 10.1038/srep07479
- Wang, S., Hou, W., Dong, H., Jiang, H., Huang, L., Wu, G., et al. (2013). Control of temperature on microbial community structure in hot springs of the Tibetan plateau. *PLoS One* 8:e62901. doi: 10.1371/journal.pone.0062901
- Wang, R., Lin, J.-Q., Liu, X.-M., Pang, X., Zhang, C.-J., Yang, C.-L., et al. (2019). Sulfur oxidation in the acidophilic autotrophic *Acidithiobacillus* spp. *Front. Microbiol.* 9:3290. doi: 10.3389/fmicb.2018.03290
- Weyrich, L. S., Farrer, A. G., Eisenhofer, R., Arriola, L. A., Young, J., Selway, C. A., et al. (2019). Laboratory contamination over time during low-biomass sample analysis. *Mol. Ecol. Resour.* 19, 982–996. doi: 10.1111/1755-0998.13011
- Wu, Y.-W., Simmons, B. A., and Singer, S. W. (2016). MaxBin 2.0: an automated binning algorithm to recover genomes from multiple metagenomic datasets. *Bioinformatics* 32, 605–607. doi: 10.1093/bioinformatics/btv638
- Xie, W., Zhang, C. L., Wang, J., Chen, Y., Zhu, Y., de la Torre, J. R., et al. (2015). Distribution of ether lipids and composition of the archaeal community in terrestrial geothermal springs: impact of environmental variables. *Environ. Microbiol.* 17, 1600–1614. doi: 10.1111/1462-2920.12595
- Zhang, Z., Wang, H., Zhou, J., Li, H., He, Z., Van Nostrand, J. D., et al. (2015). Redox potential and microbial functional gene diversity in wetland sediments under simulated warming conditions: implications for phosphorus mobilization. *Hydrobiologia* 743, 221–235. doi: 10.1007/s10750-014-2039-6